



DOCUMENT # 3139774
STATE OF MICHIGAN
KALKASKA COUNTY
RECORDED: 03/12/2018 4:49 PM
PAGES: 2
RECORDING FEES: 30.00
JOANN DEGRAAF
REGISTER OF DEEDS
BK: 4 PG: 31

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson
For corner(s) in: Kalkaska County
Field Survey Date: January 17, 2017

Original Public Land Survey Corner		Corner Code
S	T R	
S	T R	
S	T R	
S	T R	
Property Controlling Corner		
15	T 27N R 8W	Corner Code
S	T R	H6
S	T R	
S	T R	
S	T R	
Property Corner		
S	T R	Corner Code
S	T R	
S	T R	
S	T R	
Protracted Public Land Survey Corner		
S	T R	Corner Code
S	T R	
S	T R	
S	T R	

A	B	C	D	E	F	G	H	I	J	K	L	M
1	6	5	4	3	2	1						
2												
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13	A	B	C	D	E	F	G	H	I	J	K	L

Part A: Corner History

H6 – center ¼ corner section 15, T27N, R8W

– 1918 – CSR – W. S. Merrill – cedar post 4" x 4"

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

H6 – center ¼ corner section 15, T27N, R8W

Found 1" pipe of unknown origin. Position of pipe is 18' North of calculated intersection of ¼ lines. Did not find cedar post as called for by Merrill. Set a stamped 2" aluminum cap on 5/8" x 34" rebar at intersection of ¼ lines.


Part C: Field Evidence of Perpetuation or Monumentation of Corner

H6 – center ¼ corner section 15, T27N, R8W

a stamped 2" aluminum cap on a 5/8" x 34" rebar.

N08°40'E 18.22' to 1" pipe
S45°E 48.11' to set nail & tag in SW. side 10" R. Pine
S49°W 4.04' to set nail & tag in SE. side 6" Oak
N77°W 26.53' to set nail & tag in S. side 12" R. Pine

Set blue post with location tag 1' Northeast.



Joshua R. Davidson

Certifying Surveyor's Name

March 7, 2018

Date

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601