

8 0 6 7 0 8 6
TX:4046609
3/12/2018 4:40:00 PM

DOCUMENT # 3139775
STATE OF MICHIGAN
KALKASKA COUNTY
RECORDED: 03/12/2018 4:49 PM
PAGES: 2
RECORDING FEES: 30.00
JOANN DEGRAAF
REGISTER OF DEEDS
BK: 4 PG: 32

Land Corner Recordation Certificate
Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Joshua R. Davidson Field Survey Date: January 17, 2018
For corner(s) in: Kalkaska County

Original Public Land Survey Corner Corner Code
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

Property Controlling Corner Corner Code
S 14 T 27N R 8W 11
S 14 T 27N R 8W 12
S _____ T _____ R _____
S _____ T _____ R _____

Property Corner Corner Code
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

Protracted Public Land Survey Corner Corner Code
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2	6			5		4		3		2		1		2
3														3
4	7			8		9		10		11		12		4
5														5
6	18			17		16		15		14		13		6
7														7
8	19			20		21		22		23		24		8
9														9
10	30			29		28		27		26		25		10
11														11
12	31			32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

11 – SW 1/16 corner section 14 T27N R8W

– None

12 – CS 1/16 corner section 14 T27N, R8W

– None

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

11 – SW 1/16 corner section 14 T27N R8W

Set a stamped 2" aluminum cap on 5/8" x 34" rebar per BLM standard procedure.

12 – CS 1/16 corner section 14 T27N, R8W

Set a stamped 2" aluminum cap on 5/8" x 34" rebar per BLM standard procedure.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

11 – SW 1/16 corner section 14 T27N R8W

a stamped 2" aluminum cap on 5/8" x 34" rebar.

N67°E 47.95' to set nail & tag in NW. side 11" J. Pine
S30°E 24.21' to set nail & tag in SW. side 10" J. Pine
S79°W 43.52' to set nail & tag in S. side 4" W. Pine
N48°W 29.85' to set nail & tag in NE. side 6" J. Pine

Set blue post with location tag 1' Northwest


12 – CS 1/16 corner section 14 T27N, R8W

a stamped 2" aluminum cap on 5/8" x 34" rebar.

N33°E 12.05' to set nail & tag in NW. side 4" R. Pine
S73°E 21.20' to set nail & tag in N. side 15" R. Pine
S35°W 52.14' to set nail & tag in NW. side 7" R. Pine
N54°W 25.89' to set nail & tag in NE. side 13" R. Pine

Set blue post with location tag 1' North




Certifying Surveyor's Name

March 7, 2018

Date

Professional Surveyor's License No.: 46659

Prepared By: Joshua R. Davidson
Department of Natural Resources
8015 Mackinaw Trail
Cadillac, MI 49601