

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 28 N. R. 7 W.	I-8
2. PROPERTY CONTROLLING IN SECTION 23	T. 28 N. R. 7 W.	3; 10
3. MISCELLANEOUS PROPERTY IN SECTION 23	T. 28 N. R. 7 W.	Y (on line between I-9 & I-8 & 800.0' N of I-9)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 12, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on December 1, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~Y = Description of original monument and accessories used for subsequent restoration =~~

C. (continued)

Y  
Drove 1 1/4"x24" iron rod  
P. Pole N37°W 46.07  
4" B. Cherry S18°E 72.45  
Cedar post w/loc. tag  
Due E 33'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-8 Found 1" sq. bar as recovered by Cons. Power co. Survey of Sec. 23 in 1967.
- 3 Established 1/16 corner S.P. Corner falls in approximate center of N-S gravel road.
- 10 Fd. old bent 1" pipe; replaced with 1 1/4"x18" rod. Ctr. of N-S gravel road is 3'± W of corner.

Y Established NW corner of an 800'x800' exception in the SW corner of the SW 1/4-SW 1/4<sup>Sec. 23</sup> per standard section subdivision. Corner falls in center of N-S gravel road ±1'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8	Drove 3	10
Found 1" square bar,	1 1/4"x20" Rod.	Fd. old 1" pipe replaced
P.Pole N40°W 39.27	P.Pole S49°W 41.60	w/1 1/4"x18" rod
12" Maple Clstr. S84°E 78.6	14" Maple N30°E 60.8	P.Pole S22°W 80.70
16" Maple S26°E 122.8	7" Maple S81°E 39.2	P.Pole N10°W 133.25
Cedar post w/loc. tag	16" Maple S44°E 35.6	10" Maple N55°E 193.53
Due E 33'	Cedar post w/loc. tag	Cedar post w/loc. tag
	Due E 33'	Due E 33'

SIGNED BY

Carl F. Roser

DATE

10-31-77

SURVEYOR'S MICHIGAN REGISTRATION NO.

12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE


APPROVED AND SIGNED BY

CHIEF OF SURVEY PARTY

DATE

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO.

RAPID RIVER TOWNSHIP  
KALKASKA COUNTY