

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

other code #12
96 NOV -8 AM 9:25
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
REG. OF DEEDS
9580
Register of Deeds Stamp & File Number

For corners in Kent (County) Located in: Caledonia Township Corner Code # _____

1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>5N</u> R <u>10W</u>	West Witness Monument
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	364.95' West of M-7
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehhouse, in a field survey on May 3 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7C 1817	G.L.O. Notes	L. Lyon	Corner in Lake - Set Temporary Point
1992	L.C.R.C. #6552	T. Chettleburgh	Set K.C. Monument with Witness Cap
1995	L.C.R.C. #8158	K. Breitels	K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/22/96
CHAIRMAN Harry Huber

Note: This corner is not common with A-7, T5N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by T. Chettleburgh on 5/29/92 and was recorded per L.C.R.C. #6552.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7C Found a Standard Kent County Monument at the C/L of Dygert Drive 50' ± South of the C/L of 84th Street (bit.) running East and West as set by T. Chettleburgh at the intersection of the South line of Section 13 (North line Section 24) and C/L of Dygert Drive per L.C.R.C.'s #6552 and #8158. Corner is 364.95' West of M-7, T5N, R10W.

L.C.R.C. #6552

L.C.R.C. #8158

KC Remon tag NW side Power Pole N 53° E 45.78'
KC Remon tag NW side 27" Hickory N 79° E 67.05'
Con. Plat Monument S 40° E 45.81'
KC Remon tag SE side Power Pole S 33° W 39.05'
KC Remon tag SW side Tri-8" Maple N 53° W 87.57'


Nail & KC Remon. tag NW side Power Pole N 53° E 45.80'
Nail & KC Remon. tag NW side 27" Hickory N 79° E 67.05'
Nail & KC Remon. tag SE side Power Pole S 33° W 39.10'
Nail & KC Remon. tag SW side Tri. 8" Maple N 53° W 87.63'
Plat Monument S 40° E 45.86'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7C Standard Kent County Monument

Nail & K.C. remon. tag on NW side Power pole N 53° E 45.80'
Nail & K.C. remon. tag on NW side 27" Hickory N 79° E 67.05'
Nail & K.C. remon. tag on SE side Power pole S 33° W 39.10'
Nail & K.C. remon. tag on SW side Tri. 8" Maple N 53° W 87.63'
Plat Mon. S 40° E 45.86'
K.C. Mon. @ L-7, T5N, R10W, West 2280.15'



Signed by Randy J. Kolehhouse Date 10/8/96
EARTH TECH
Surveyor's Michigan License No. 25854