

SEP 13 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent
(County)

Located in:

Corner Code #

1. Public Land Survey

T 5N R 12W

1-4

T R

T R

T R

2. Property Controlling S T R

in Section S T R

3. Miscellaneous S T R

Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Randy Kolehouse, in a field survey on April 6 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1-4 1831 G.L.O. Notes Mullett
1946 Wit. Map K.C. Surveyor
1971 L.C.R.C. #40 Williams & Works
1980 L.C.R.C. #1544 Exxel Engineering
1992 L.C.R.C. #6328 Chris Marschall

Set Post
3" Iron
Found 3/4" Iron in Mon. Box
Found 1" Iron in Mon. Box/Set K.C. Monument
K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 5/29/95

CHAIRMAN Harry Shuber

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 2/23/80 and was recorded per L.C.R.C. #1544.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-4 Found standard Kent County Monument on C/L of 72nd Street running E-W and in C/L of S.B. lane of Burlingame Avenue running N-S per L.C.R.C.'s #1544 and #6328 as set by Exxel Engineering in place of a 1" iron in monument box they found which checked L.C.R.C. #40 and K.C. Surveyor's Wit. Map.

L.C.R.C. #1544

L.C.R.C. #6328

Nail & tag in NE sde 26" Walnut (2' above ground) N68°W 48.10'
Nail & tag in E sde 8" White Birch (.5' above ground) S22°W 92.60'

Nail & Tag NE sd. 28" Walnut N 68° W 48.05'
Nail & Tag E sd. 12" White Birch S 22° W 92.58'
Nail & Tag NE sd. U.P. N 33° W 38.03'
Nail & Tag NW sd. U.P. S 40° W 75.97'
Nail & Tag SE sd. Guy Pole N 43° E 39.61'
In center of South Bound Traffic Lane

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


1-4 Standard Kent County Monument

Nail & K.C. remon. tag on NE side 28" Walnut N 68° W 48.05'
Nail & K.C. remon. tag on E side 12" White Birch S 22° W 92.58'
Nail & K.C. remon. tag on NE side Util. pole N 33° W 38.03'
Nail & K.C. remon. tag on NW side Util. pole S 40° W 75.97'
Nail & K.C. remon. tag on SE side Guy pole N 43° E 39.61'
In center of south bound traffic lane

Signed by Randy J. Kolehouse

Date 8/21/95

Surveyor's Michigan License No. 25854



STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 AUG 28 AM 10:52
REG. OF DEEDS
8627

Register of Deeds Stamp & File Number

