

SEP 1 8 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent
(County)

Located in:

Corner Code #

1. Public Land Survey

T 5N R 12W

I-6

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
55 AUG 28 AM 10:52
REG. OF DEEDS
8629

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on April 6 19 95,
do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required
in the current manual of survey instructions of the United States Department of the interior, Bureau of
Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,
4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered,
found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Wit. Map	K.C. Surveyor	Iron
	1973	L.C.R.C. #472	Williams & Works	Found 1/2" Iron
	1981	L.C.R.C. #2299	Nederveld & Jonker	Found 1/2" Iron/Set K.C. Monument
	1991	L.C.R.C. #6330	Chris Marschall	K.C. Monument

KENT COUNTY
PEER APPROVED 5/26/95
CHAIRMAN Harry Thuermer

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Nederveld & Jonker on 9/2/81 and was recorded per L.C.R.C. #2299.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found standard Kent County Monument 1.0' West of west edge of bit. of Burlingame Avenue running N-S per L.C.R.C.'s
#2299 and #6330 as set by Nederveld & Jonker in place of a 1/2" iron they found which checked L.C.R.C. #472 and K.C.
Surveyor's Wit. Map.

L.C.R.C. #2299

Nail & K.C. Remon. tag S side P. pole W 12.91'
NW cor. hse fnd. S80°E 125.46'

L.C.R.C. #6330


Nail & Tag W sd. 22" Walnut S 25 W 40.27'
Nail & Tag S sd. P. pole S 90 W 12.86'
NW cor Hse Fndn. S 80 E 125.44'
Nail & Tag E sd. 10" Cedar N 12 W 79.35'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence
of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 Standard Kent County Monument

Nail & K.C. remon. tag on W side 22" Walnut S 25° W 40.27'
Nail & K.C. remon. tag on S side P. pole S 90° W 12.86'
NW cor. hse. fndn. S 80° E 125.44'
Nail & K.C. remon. tag on E side 10" Cedar N 12° W 79.35'



Signed by Randy J. Kolehouse
EARTH TECH

Date 8/21/95

Surveyor's Michigan License No. 25854