

SURVEY &
REMONUMENTATION

OCT 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KEWEENAW
(County)

Located In

Corner Code #

1. Public Land Survey

56N
T 57N R 32W
T 57N R 32W
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

H-1501
I-12

2. Property Controlling
In Section

3. Miscellaneous
Property in Section

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTER'S OFFICE

County of Keweenaw } SS

Received for Record, the 29th

day of July A.D. 1997

at 10:00 o'clock A.M., and Recorded

in Liber _____ of LCR

on page 167

Maelynn W. Sigurdson
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R. W. CRAMPTON, in a field survey on MAY 30 19 85
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 SOUTH 1/4 CORNER-SET POST-SUGAR 10 N50E 25, SUGAR 10 N46W 24.

I-12 EAST 1/4 CORNER-SET POST-SUGAR 18 S40W 21, Y. BIRCH 8 N40E 27.

Ratified by Peer Group
In accordance with P.A. 345


Co. Rep. Maelynn W. Sigurdson

Date 7/28/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 SOUTH 1/4 CORNER-1 1/2" IRON PIPE FOUND AND SET WITH 4" BRASS CAP.

I-12 EAST 1/4 CORNER-1" IRON PIPE FOUND IN THE CENTERLINE OF AN OLD ROAD AND ON A
PROJECTION OF AN OLD FENCE EAST OF THE CORNER AND SET WITH 4" BRASS CAP.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 THE 1 1/2" IRON PIPE WITH 4" BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:
14" OAK TREE N15 W 6.55', 8" OAK TREE N25 E 7.96',
8" OAK TREE S81 E 14.86', 7" OAK TREE S30 W 8.37'.

I-12 THE 1" IRON PIPE WITH 4" BRASS CAP WAS WITNESSED WITH SURVEY TAG NAILED TO:
8" TWIN MAPLE TREE S79 E 18.85', 12" MAPLE TREE S13 E 66.31',
5" MAPLE TREE S40 W 36.10', 8" ASPEN TREE N70 W 19.60'.

Signed by Robert W. Crampton

Date JULY 22, 1997

Surveyor's Michigan License No. 24591