

STATE OF MICHIGAN  
COUNTY OF KALAMAZOO  
RECEIVED FOR RECORD  
94 MAR 17 PM 3 39

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KALAMAZOO TWP.

KALAMAZOO (County) Located In: Corner Code ##

1. Public Land Survey	T 2 S R 11 W	E-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*James B. Gump*  
CLERK-REGISTER

LIBER 1 PG 1127

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat  
5. Private Claims

I, Allen H. McMachen a field survey on February 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1880's - F. Hodgeman C.S. placed Clay Tile Post during official Township Remonumentation.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found broken top section of Clay Tile, removed top section and found bottom section of Tile.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Found Clay Tile is accepted as a careful and faithful perpetuation of the original corner. Placed Harrison Monument over existing bottom section of Clay Tile, accessories:

Nail & Tab (3.5' high) in East face  
Nail & Tab in South face Multi-stemmed  
Nail & Tab in South face  
Nail & Tab (7' high) in Northwest face

24" Maple N. 35 deg. E. 24.32'  
Basswood N. 65 deg. E. 2.35'  
12" Maple N. 80 deg. E. 18.87'  
30" Maple SOUTH 30.86'

*12-28*  
RATIFIED  
BY KALAMAZOO COUNTY  
REMONUMENTATION  
PEER GROUP  
3-3-94



Signed by Allen H. McMachen  
Surveyor's Michigan License No. 16935

Date 3/15/94