

SURVEY &  
REMONUMENTATION

MAY 18 1998

LIBER 004 PAGE 0125

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in  
Lake

(County)

Located In:

Corner Code #

1. Public Land Survey

T	18N	R	13W	E-9
T		R		
T		R		
T		R		
T		R		
S		T		
S		T		
S		T		
S		T		

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Robert L. Wetherell, in a field survey on Jan. 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-9 - Section corner common to Sections 20, 21, 28 & 29, T18N, R13W, Webber Twp., Lake Co., Mi.

1838 - S. Sibley, G.L.O.

#1 - 10" Pine N57°E 28 Links

#2 - 8" Pine S48°W 9 Links

1908 - George West, Deputy Co. Sur.

"Original witness stumps standing".

#3 - 8" W. Oak N29°15'W 112-1/4 Links

#4 - 12" Pine S71°E 110 Links

1937 - William Downey

1/2" rod with bricks "Located in course of making highway survey".

#5 - 12" Pine N30°W 42.42'

#6 - 14" Oak S84°W 45.71'

#7 - 12" Pine S71°E 48.89'

1968 - George Blass, LS 5489

Used corner to make plat of "Haven's Rest".

1972 - Robert Griffin, LS 13584

L.C.R.C. - Liber 02, Pg. 81.

Found 1/2" rod and bricks. Replaced with 5" Concrete Monument.

#8 - P. Pole N70°E 64.68'

#9 - Cedar Post S45°W 46.7'

#10 - S.E. Cor. Brick Fireplace

N50°W 89.64'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 - Section corner common to Sections 20, 21, 28 & 29, T18N, R13W, Webber Twp., Lake Co., Mi.

I found Griffin's 5" Concrete Monument in the intersection of roads North, South East and West.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Gone, #6 Gone #7 Gone, #8 Found in good condition, #9 Found in good condition, #10 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345

CHAIRMAN R. X. W.

DATE 4.9.98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 - Section corner common to Sections 20, 21, 28 & 29, T18N, R13W, Webber Twp., Lake Co., Mi.

I accepted the 5" Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

15" W. Oak N25°W 80.0' (Center of tree)

14" W. Oak S47°W 57.83' (60d spike in N.W. side)

S.E. corner Brick Fireplace N44°W 89.56' - #10

P. Pole N74°E 64.62' (nail and cap in N. side) #8

12" B. Oak S54°E 101.58' (60d spike in S.W. side)

Signed by Robert L. Wetherell

Surveyor's Michigan License No. 24624

Date 4.14.98

