

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Lake Located In Corner Code #
1. Public Land Survey T 19N R 12W K10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No: Recorded Plat:
5. Private Claims:

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on June 16, 2014 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Table with 13 rows and 13 columns (A-M). Contains numbers 1-36 and a black dot at row 10, column K.

A. Description of original monument and accessories and/or subsequent restoration:

K10 - 1838 - GLO - S. Sibley - Set 1/4 Post
1) Cedar 6" N6°W 3 L.
2) Hemlock 8" S6°E 9 L.
- 1973 - LCRC - L. C002, p. 155 - C. F. Roser (PS #12028)
Reestablished corner per Standard BLM instructions.
Set DNR Mon. and Cedar Gd. Post;
3) Maple N55°E 22.9'; 4) 4" Cedar S18°E 32.8';
5) 10" Hemlock S86°W 36.9'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K10 - 1/4 Corner common to Section 25 & 26, T19N, R12W - Fd. 4" Dept. of Conservation (DOC) Aluminum Cap on 1" iron pipe per Roser. No GLO evidence was found. Condition of witnesses: #1 & 2 are gone; #3 & 4 are OK; #5 - Dead. DOC Monument accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K10 - 4" DOC Aluminum Cap on 1" iron pipe
S52°E 7.13' to set nail & tag in NE side 9" Sugar Maple
S16°E 32.90' to set nail & tag in W side 10" Cedar (#4)
S86°W 21.07' to set nail & tag in S side 4" White Pine
N18°W 7.55' to set nail & tag in W side 10" Sugar Maple scribed 'XBT'
N52°E 23.21' to set nail & tag in NW side 14" Red Maple (#3)
Found rotten cedar post NW of monument 0.9' to the face. Set Blue Composite Post 1' South.



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 8/12/2014