

AUG 31 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0207

JUL 23 3 05 PM '99

Shirley H. Dechow
REGISTER OF DEEDS

For corners in
Lake

Located in:

Corner Code#

1. Public Land Survey T 20N R 11W K-9
T R
T R
T R
2. Property Controlling s T R
in Section s T R
3. Miscellaneous s T R
Property in Sec. s T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on June 2, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

K-9 - Section corner common to Sections 23, 24, 25 & 26, T20N, R11W.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - S. Sibley, G.L.O.

- #1 - 12" Hemlock S70°W 23 Links
#2 - 12" Elm N83°E 16 Links

1919 - G. H. Johnson, Co. Sur.

- #3 - ⓧ On cement culvert N29°W 24'

1975 - J. Erickson, LS 16929

- L.C.R.C. - L. 02, Pg. 261
"Set 5/8" Rod at prop. distance East, West and North."
#6 - S.E. cor. of Store N60°W 102.0'
#7 - S.W. Cor. House N45°E 74.1'
#5 - 30" Maple S50°E 102.9'

1911 - G. H. Johnson, Co. Sur.

- #3 - ⓧ On top of cement culvert N30°W, 36 1/2 Links
#4 - 18" Elm S59°W 70 Links
#5 - Maple S51°E 159 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found Erickson's 1/2" capped iron in centerline road North and South and 4 feet North of centerline road East and West. I found Johnson's chiseled "X" in the concrete culvert. I set the corner using Johnson's "X" and Johnson's Maple Tree (accessory #5). Corner falls N26°W 2.46' from Erickson's 1/2" rod. I removed Erickson's Iron.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Gone, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" x 24" re-bar with Lake County Remon Cap and is accepted as a careful and faithful reestablishment of the position of the original corner.

- Guy Pole S53°W 43.97' (P.K. Nail in East side)
P. Pole S15°W 151.32' (P.K. Nail in West side)
40" Maple S45°W 105.04' (Found 60d Spike in South Side) #5
"X" in Concrete Culvert N26°W 24.09'
S.E. corner of Store (old) N61°W 99.79'

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *RJW*
DATE *7-20-99*

Signed by Robert L. Wetherell

Date July 21, 1999

Surveyor's Michigan License No. 24624

