

MAY 18 1998

LIBER004 PAGE0137

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970For corners in
Lake

(County)

Located In:

Corner Code #

1. Public Land Survey

T 20N R 12W

D-5

2. Property Controlling
in Section3. Miscellaneous
Property in Sec.S T R
S T R
S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Robert L. Wetherell, in a field survey on March 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5 - 1/4 Corner common to Sections 8 & 17, T20N, R12W, North Newkirk Twp., Lake Co., Mi.1838 - S. Sibley, G.L.O.

#1 - 4" Pine N78°E 46 Links

#2 - 3" Pine S12°W 13 Links

1973 - Clinton E. Cole, LS 17615

L.C.R.C. - Liber 02, Page 179

Found Iron pin/set concrete monument

Survey recorded Liber 01, Pg. 339

#3 - P. Pole S28°E 37.73'

#4 - 6" J. Pine N38°W 54.89'

#5 - 14" J. Pine S22°W 102.72'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 - 1/4 Corner common to Sections 8 & 17, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

I found Cole's 4" Concrete Monument in centerline of East and West road and 50 feet more or Less West of road to North. At this date the Lake County Road Commission is relocating the road North, so this corner will be in the intersection.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Gone, #5 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 - 1/4 Corner common to Sections 8 & 17, T20N, R12W, North Newkirk Twp., Lake Co., Mi.

I accepted the 4" Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

P. Pole S28°E 37.69' (Found nail & cap) #3

16" Tw. B. Oak S73°W 143.20' (60d spike in N. side)

6" W. Pine S11°E 42.37' (60d spike in E. side)

6" W. Pine S26°E 71.95' (60d spike in E. side)

14" B. Oak N38°E 136.08' (60d spike in N.E. side)

Signed by Robert L. WetherellSurveyor's Michigan License No. 24624RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345CHAIRMAN R.L.W.
DATE 4-9-98Date 4-14-98