

MAR 29 1999

1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: DEERFIELD TWP.

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 09N R 10E	C-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD

98 DEC 22 PM 3:44

Melissa De Vaux
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

425
Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on JUNE 30 1998,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5		4		3		2				
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1834 GLO; BURNHAM, D.S.; INTERSECTED N BNDY 2CH 68LKS E; BEECH 8 S29°W 36 LKS, BEECH 12 S48E 77 LKS.
1906 SICKLESTEEL, C.S.; SURVEY SEC. 5, T9N-R10E; PG.8-9; STAKE; PINE STUMP 33 S58W 155LKS, PINE STUMP 36
S32W 173LKS.
1973 KAY, P.S.#14096; SURVEY L.002, PG.481-3; NO OBJECT STATED; N50°W 40.45' NAIL IN T.P., S45°E 63.38' NAIL IN
T.P., S60°W 62.40' NAIL IN T.P.
1977 GRAVLIN, P.S.#23510; SURVEY L.004, PG.152; NO OBJECT STATED; SAME WITS AS 1973 KAY SURVEY ABOVE
1985 ELRICH, P.S.#18986; SURVEY L.007, PG.057; FND. 1/2" IRON; SAME WITS AS 1973 KAY SURVEY ABOVE
1989 GRAVLIN, P.S.#23510; LCRC L.004, PG.221; FND. IRON; SAME WITS AS 1973 SURVEY ABOVE
1992 GRAVLIN, P.S.#23510; SURVEY L.009, PG.961; FND. 1/2" RE-ROD; N40°E 22.90' CMP, S25°E 64.05' NW COR PED.,
S60°W 62.40' NAIL IN T.P.
1995 GRAVLIN, P.S.#23510; SURVEY L.0010, PG.0911-2; FND. 1/2" IRON; SAME WITS AS 1973 SURVEY ABOVE
1995 GRAVLIN, P.S.#23510; SURVEY L.0010, PG.0983-5; FND. 1/2" IRON; SAME WITS AS 1973 SURVEY ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 ROWE; FIELD, PS#37276; FND. 1/2" ROD RECOVERED 1 PREVIOUS WITNESS WHICH INDICATES THAT FND.
ROD IS IN SAME POSITION AS 1992 IRON CITED IN SECTION A ABOVE

C-1 TO D-1 2665.43' (KAY '73)
2665.04' (ROWE '98)

C-1 TO C-13 176.88' (G.L.O.)
157.04' (ROWE '98)

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION 9-17-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 SET STD. REMON. CAP ON FND. 1/2" ROD
S60°E, 62.10' NAIL W/ FLAG. IN N. FACE FENCE POST
S35°E, 51.75' P-K NAIL W/ TAG IN E. FACE FENCE POST
N37°W, 94.85' NAIL W/ REMON TAG IN SW FACE 18" MAPLE
N38°E, 23.02' CHIS. + ON W. END 12" CMP

Signed by Jonathan M. Field Date 10-28-98
Surveyor's Michigan License No. 37276

