

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>10W</u>	<u>C5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 06/28/2010 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C5) Corner common to Sections 7-8-17-18. 1974 - Billy D. Buckler RLS reestablished the corner from  
corners East, West, and North. Set 1"IDx36" iron pipe with 4" alum. MDNR cap. 14" W.Pine S15E  
86.0', 10" Apple N60W 60.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C5) Found the 1974 monument disturbed. It appears to have been pulled out of the ground and  
subsequently reinserted at an incorrect position near to the 1974 position. At the position for the  
corner, found a hole in the soil corresponding to the 1974 position, at record bearing and distance  
from the 1974 NBTs. The NBT W.Pine SE is in good condition. The NBT Apple NW is dead. Reinstalled  
the monument of record at the 1974 position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C5) 1"IDx36" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
24" W.Pine S10E 86.45' mrkd "S17" 1974 NBT  
12" Maple East 60.6' mrkd "S8 NBT"  
9" R.Pine S27W 14.65' "S18 NBT"  
8" Cherry N06E 57.4' "S8 NBT"  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/26/2010  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division