

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 10W	B3
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 06/28/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B3) Quarter corner common to Sections 6 and 7. 1853 - Established by Geo.H.Cannon Deputy Surveyor
in a correction survey of this township N89 deg. 27' E 39.16 chains from Section corner A3 and N89
deg. 26'W 40.34 chains from Section corner C3. Beech 12" N34W 12 links, Beech 8" S70E 21 links.
1974 - Billy D. Buckler RLS reestablished the corner by single proportionate measure between two
Section corners. Set 1"IDx36" I.pipe with 4" alum. Department cap. 12" W.Pine N67E 8.9', 14"
Spruce, West 6.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B3) The original post and accessories were not recovered. Found the 1974 monument in good condition
and at record bearing and distance from the 1974 witnesses. The W.Pine NBT NE is in good condition.
The Spruce NBT West has fallen. Found the easting of the corner to be in substantial accord with the
record. The monument is approximately 24' north of a position which would make the deflection at
this corner equal to the record GLO deflection between section corners. I note that land owners to
the east in Section 7 have used this position to establish the section line in the course of making
improvements to property. I accept the monument as a careful and faithful reestablishment of the
position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B3) Found 1"ID I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
26" W.Pine N73E 9.05' mrkd "1/4 S" 1974 NBT
16" triple W.Pine S78W 60.5' mrkd "1/4S NBT"
10" Maple in clump N09W 23.1' do
6" Balsam S11E 19.6' do
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/26/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983