

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce Located In: Corner Code #
(County)

1. Public Land Survey T 48N R 11W D1
T 49N R 11W D13 (same corner)
T R
2. Property Controlling in Section S T R
S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/08/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Section 5 T48N-R11W and Section 32 T49N-R11W. 1841 - Established by John Burt, Deputy Surveyor, midway and on the Township line between Section corners 40.00 chains east and west. Set post. Spruce 12" N50E 22 links, Fir 10" N50W 16 links. 1979 - Remonumented by Billy D. Buckler RLS midway and on line between Section corners: "Found an iron pipe, 6.0' South and 5.0' West. This is not a Marcus Schaaf R.L.S. pipe. Don't believe this pipe was intended for the 1/4 corner". Set 1" pipe with 4" aluminum cap, buried in S. edge E-W firelane. 15" R.Pine S14W 21.4', 12" R.Pine N53W 40.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The 1979 monument was not recovered. Found the 1979 NBTs in place, in good condition, with overgrown blazes. Reestablished the 1979 position at record bearing and distance from these NBTs and check measured east and west to adjacent Section corners and found the 1/4 corner position to be substantially as described in the 1979 record. Accepted the 1979 position as a careful and faithful reestablishment of the position of the original corner. Placed a new monument to perpetuate that position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx36" I.pipe with plastic cap stamped "MICH DNR LS 33986", below surface of firelane. Set measuring nail with MDNR tag in the side of:
19" R.Pine S17W 21.95' mrkd "1/4S" 1979 NBT
15" R.Pine N54W 40.42' do do
10" W.Pine N72E 57.67' mrkd "1/4S NBT"
9" R.Pine S76E 55.0' do
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 02/17/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities