

SURVEY &
REMONUMENTATION

FEB 26 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

FILED

LIVINGSTON Located In: Corner Code #
(County)

1. Public Land Survey T 1N R 3E I-09
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

2000 NOV 15 A 9:30

NANCY HAYLAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC #1381m

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, DARRELL D. HUGHES, in a field survey on October 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6			5			4		3		2	1
3												
4	7			8			9		10		11	1
5												
6	18			17			16		15		14	1
7												
8	19			20			21		22		23	2
9												
10	30			29			28		27		26	2
11												
12	31			32			33		34		35	3
13												

UNADILLA TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825, Sylvester Sibley, Deputy Surveyor
Black Oak 20 inch diameter, bears North 3 degrees East, 44 links
Black Oak 10 inch diameter, bears South 40 degrees West, 84 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1 inch iron pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-09, T1N-R3E, UNADILLA, replaced existing corner with 1-1/4" x 36" iron pipe, affixed with 2" diameter brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834," and is accepted as a careful and faithful reestablishment of the position of the original corner.

138 DEG. 41.97' SET NAIL/TAG SW/S 36" OAK
010 DEG. 5.30' SET NAIL/TAG E/S 18" OAK
270 DEG. 31.07' SET NAIL/TAG S/S 20" OAK
063 DEG. 43.65' SET NAIL/TAG W/S TRIPLE 8"-10" OAK

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 9-6-00 CO. REP JED

Signed by 
Surveyor's Michigan License No. 19834

Date October 12, 2000