

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON Located In: Corner Code #
(County)

1. Public Land Survey T 1 N R 4 E I-05
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

1999 JUN -4 P 12: 55

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #1023m

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, JACK K. SMITH, in a field survey on MARCH 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1825 SIBLEY SET POST
B. OAK 13 N 83 W 62 (40.9')
B. OAK 11 N 54 E 30 (19.8')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" REROD WITH BOSS CAP. THIS POSITION IS THE ONLY ONE THAT APPEARS TO HAVE BEEN USED.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


I-05 CORNER COMMON TO SECTIONS 10, 11, 14 AND 15, T1N, R4E, PUTNAM TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:
RESET FOUND 1/2" REROD WITH 1 1/4" X 36" STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP
WITH SURVEYOR #35999 @ 1/2 FOOT ABOVE THE SURFACE OF SURROUNDING GROUND.

N10°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE FORKED 50" OAK 74.11'
EAST NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 8" CHERRY 30.02'
SOUTH NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 12" POPLAR 7.23'
N15°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 6" OAK 18.97'

Signed by

Date 3-26-1999

Surveyor's Michigan License No. 35999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 21
REVISED MAY 14, 1975 REVISED JAN. 1983
REVISED OCT. 1995

PA. 345 1980, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-3-1999 CO. REP JED