

FILED

Oct 16 11 44 AM '95

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

LIVINGSTON  
(County)

Located In:

Corner Code ##

Public Land Survey

T 1N R 4E

M-9

Property Controlling  
in Section

S T R

Miscellaneous

S T R

Property in Sec.

S T R

L.S.C.# 500m

Register of Deeds Stamp &amp; File Number

Lot No. , Recorded Plat

Private Claims

DARRELL HUGHES, in a field survey on OCT. 4  
JANUARY 24, 19 95,

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO: 1823, Joseph Wampler, Deputy Surveyor  
Black Oak 18", South 40 degrees West, 194 links  
Black Oak 17", North 37 degrees East, 196 links

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PUTNAM TWP.

SURVEY &  
REMONUMENTATION

NOV 27 1995

Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 4" diameter concrete monument

COMMISSION

\*Additional descriptions and historical information on back of this sheet.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9, T1N, R4E, PUTNAM, left existing corner monument in place, affixed top with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
072 DEG. 20.26' SET NAIL/TAG S/S 15" ELM.  
154 DEG. 18.26' SET NAIL/TAG N/S 15" OAK.  
265 DEG. 10.24' SET NAIL/TAG S/S 6" OAK.  
002 DEG. 41.37' SET NAIL/TAG E/S TWIN 20" CHERRY.

Signed by Amell Hughes Date October 5, 1995Surveyor's Michigan License No. 19834

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

PUTNAM TOWNSHIP, T1N, R4E

M-9, NORTHEAST CORNER SEC. 25, SOUTHEAST CORNER SEC. 24

FIELD: FEBRUARY 1995

FOUND 4" DIA. CONC. MONUMENT IN DOWNED N,S AND W FENCE LINE. MEASURES  
137.18' (137.16' R.PLAT) (153.78' GLO) NORTH TO FOUND 4" DIA. CONC.  
MONUMENT FOR A-9 HAMBURG.  
POOR FOR GPS.

1823 corner first set by Joseph Wampler, U.S. Deputy Surveyor....."North  
on East boundary Section 25, 80 chains, set post." P.7

1858 Ezra Fairchild, County Surveyor, identifies A-9, Hamburg. P.9

1874 Miles Bullock, County Surveyor, surveys and divides Section 25.  
P.10-11

1965 Lyle Munsell identifies A-9, Hamburg.

1973 Oscar Boss finds "iron" and files Act 74. P.13-15

1975 Oscar Boss sets A-9, Hamburg. P.16-17

1981 Herb Hunzell plats "Pinckney School Acres", sets monuments for A-9,  
Hamburg and M-9, Putnam. P.18.

1995 Hughes measurements and corner witness. P.21-22