

SURVEY & REMONUMENTATION

JUN 29 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

APR 26 9 44 AM '95

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

For corners in

Livingston
(County)

Located in:

Corner Code ~~##~~

- | | | | | | |
|------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | 3N | R | 3E | K-6 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

L.S.C. #387m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles E Garlock, in a field survey on April 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey dated: April 15, 1825 by S. Sibley DS


GLO Witnesses: W09-N86W-25 lks
B08-N34E-24 lks

Additional historical data on rear of sheet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/4" X 24" I. Pipe

3/4"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6: W 1/4 corner Sec. 13 T3N-R3E, Handy Twp. Lic. Co. MI; reset foud I. Pipe with a 1 1/4" X 36" breakaway I. Pipe with a Liv. Co. Remon brass cap on top at -0.5'
S80E-51.27'-so & tag S/s 15" Maple
S77E-37.55'-sp & tag S/s 15" Maple
S25E-35.52'-sp & tag SW/s 40" Maple
S20W-81.14'-sp & tag E/s 42" Maple
S27W-113.00'-sp & tag NE corner of House Foundation
Corner is on c/l of North-South Road

PA. 345 1180, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 3/1/95, CO. REP JED

Signed by

Charles E Garlock

Date April 20, 1995

Surveyor's Michigan License No.

14762


CORNER SUMMARY

K-6: W 1/4 COR. SEC. 13, T3N-R3E, HANDY TWP., L.V. CO., MICHIGAN

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.

EARLIER SURVEYS BY E GRANT (1878) AND I TELLER (1886 & 1887) CALL FOR A DRAG TOOTH AND BRICK, NONE OF THE WITNESSES REMAIN. IN 1935 C GORDON FOUND THE CORNER WITH THREE OF THE OLDER 1878-87 WITNESSES, BUT SAID NOTHING OF THE TYPE OF CORNER FOUND. SURVEYS FROM 1967 TO PRESENT BY BENTON, BOSS, HUGHES, MDOT, ROON AND MYSELF FOR THE MOST PART REFER TO A FOUND 3/4" I PIPE, SOME CALL IT A 1/2" I PIPE {PAR}. WITNESSES THAT REMAIN BY BENTON, BOSS, HUGHES, ROON AND MYSELF CHECK TO THE EXISTING 3/4" I PIPE NEAR THE CENTERLINE OF A GRAVEL ROAD. FOUND NO OCCUPATION TO THE EAST, BUT ALONG THE CENTERLINE OF VAN RIPER ROAD FURTHER TO THE WEST WHEN IT RETURNS TO THE 1/4 LINE. MEASURES NORTH TO THE NW COR. ARE: 2661.85 BY BENTON, 2661.90 BY MYSELF AND 2658.15 BY E GRANT. SOUTH TO THE SW SEC. COR.: 2653.75 FT BY BOSS, 2653.70 BY HUGHES, 2657.2 BY GORDON, 2653.69 BY MDOT AND 2653.75 BY MYSELF. EAST TO THE CENTER OF SEC. 13: 2625.52 BY BOSS, 2625.63 BY BENTON AND 2624.88 BY MYSELF. WEST TO THE CENTER OF SEC. 14: 2623.41 BY MYSELF, 2622.72 BY BOSS AND 2622.78 BY HUGHES. FOUND THREE ACT 74'S RECORDED AND 15 ACT 132'S RECORDED TO THIS CORNER. GPS OBSERVATION IN QUADRANTS I AND IV ONLY.

CHARLES E GARLOCK
PS 14762



K6HAN95

3N-3E K-6
4