

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code #

1. Public Land Survey

T 3N R 4E

B-11

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

AUG 22 @ 51 AM '95
NANCY HAYLAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

FILED

L. S. C. #424m
Register of Deeds Stamp & File Number

Charles E Garlock, in a field survey on August 17, 1995

Do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO survey dated April 15, 1825 by S Sibley, DS,

GLO witnesses: Tam 7-N2E-8 lks

Tam 5-S29½E-10 lks

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Additional historical survey data on rear of sheet

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" I. Rod at the base of a wood corner post with fence lines North, South, and East.


SEARCHED
SERIALIZED

OCT 6 1995

COMAIR

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11: N 1/4 corner Section 31, T3N-R4E, Howell Twp. Liv. Co. MI, reset found 1/2" I. Rod with 1 1/4" X 36" I. Pipe with Liv. Co. Remon brass cap on top at +0.5'
S80W-82.06'-sp & tag N/s 40" maple
North-25.22'-sp & tag W/s 10" Elm
S5W-13.01'-sp & tag W/s 12" Oak
S10W-16.68'-sp & tag W/s 14" Oak
Fence lines: North, South & East.



igned by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date August 17, 1995

PA 245 1990, APPROVED BY LIVINGSTON COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983