

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON

(County)

Located In:

Corner Code #

1. Public Land Survey

T3N R4E

G10

2. Property Controlling
in Section

S

T

3. Miscellaneous
Property in Sec.

S

T

4. Lot No. , Recorded Plat

5. Private Claims

I, CHARLES E. GARLOCK, in a field survey on AUG, 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED: APRIL 15, 1825 BY S SIBLEY, DS
GLO WITNESSES: WO 20-S48½E-45 LKS
WO 20-N59W-142 LKS.

ADDITIONAL DATA ON REAR OF SHEET.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ½" I. ROD 8-9' WEST OF CENTERLINE OF NORTH-SOUTH ROAD AND 3' SOUTH OF REMAINS OF OLD ROAD TO THE WEST, NO OCCUPATION TO THE EAST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G10: EAST ¼ COR. SEC. 28, T3N-R4E, HOWELL TWP. LIV. CO. MI., RESET ½" I. ROD WITH 1¼" X36" BREAKAWAY I. PIPE WITH LIV. CO. REMON BRASS CAP ON TOP,
N43W-45.38'-SP & TAG E/S 40" OAK
N62W-63.08'-SP & TAG N/S 40" OAK
S88W-90.10'-NE CORNER CONC. BLOCK BLDG "TOMATO BROS."
N5W-148.02'-SP & TAG E/S 40" OAK

Signed by

Charles E. Garlock

Date

AUGUST 8, 1998

Surveyor's Michigan License No.

14762


1998 AUG 20 P 4:42

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #857m

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code ##

1. Public Land Survey T 3N R 4E G-11
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED
SEP 1 3 29 PM '94
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C.# 247m
Register of Deeds Stamp & File Number

I, Charles F Garlock, in a field survey on May 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey dated: April 15, 1825, by S Sibley, DS
GLO witnesses: W011-N351/2E-0.18 ch
W012-S681/2E-0.30 ch

See additional data on rear of sheet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument as per plats of "Fox Hills" and "Crancroft" subdivisions, by Lyle W Munsell

SURVEY &
REMONUMENTATION

SEP 26 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11: NW cor. Sec. 34 T3N-R4E, Howell Twp. Liv. Co. MI, Set 1/2" X 48" I. Rod inside of concrete Mon. with 3/4" I. Pipe and set Liv.Co. Remon brass cap on top.
North-2.24'-sp & tag W/s RR tie post
N10E-6.00'-sp & tag E/s 30" Oak
East-31.53'-sp & tag N/s 24" Hickory
N80W-49.88'-sp & tag N/s 8" Hickory
Mon. is in ROW of CSX RR near the top of a bank



Signed by Charles E. Garlock Date August 19, 1994

Surveyor's Michigan License No. 14762

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 18 May 94, CO. REP RAB