

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 JUL 29 P 12: 28

For corners in

LIVINGSTON

(County)

Located In:

Corner Code #

1. Public Land Survey

T___ R___
T___ R___
T___ R___
T___ R___

2. Property Controlling
in Section

S___ T___ R___
S___ T___ R___

3. Miscellaneous
Property in Sec.

S 28 T 3N R 6E
S___ T___ R___

009

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

cls # 1048m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on JULY 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED: MAY 24, 1823 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN
GLO WITNESSES: "COR. SECS. 27, 28, 33 & 34 IN LAKE, NO POST OR BEARINGS"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 IS LOCATED ON THE EXTENSION OF A LINE EAST FROM F-11 TO G-11, 1781.13 FEET FROM A POINT ON THE WEST LINE OF "HARTLAND SHORES ESTATES NO. 2" RECORDED IN LIBER 12 OF PLATS, PAGES 10 & 11 OF LIV. CO. RECORDS. SAID POINT LOCATED ON THE WEST LINE OF OUTLOT C 7.77 FEET N'LY FROM THE SW CORNER THEREOF.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1" X 36" WITNESS PIPE ON THE NORTH LINE OF SECTION 33 204.82 FEET EAST FROM F-11 AND 1781.13 FEET WEST OF G-11, WITH A BRASS WITNESS CAP ON TOP
S45E-6.15'-SP & TAG N/S 36" FORKED CHERRY
N15W-20.83'-SP & TAG W/S 10" CEDAR
N10W-3.33'-2" ANGLE IRON IN CONCRETE
WEST-17.83'-SP & TAG N/S 9" CHERRY


Signed by

Charles E. Garlock

Surveyor's Michigan License No.

14762

Date JULY 19, 1999



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 5-5-1999 CO. REP *LED*