

SURVEY & REMONUMENTATION

FEB 26 2001

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

1. Public Land Survey

T 4 N R 3 E

J-07

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

2000 SEP 28 A 9:18

HANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC #1287m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, JACK K. SMITH, in a field survey on JULY 20, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, SURVEY DATED: APRIL 15, 1825 BY S. SIBLEY
GLO WITNESSES: SUGAR MAPLE 8" N89W 19.80'
BEECH 18" N54E 9.90'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD IN OLD FENCE POST HOLE SURROUNDED BY STONES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


J-07: S 1/4 CORNER SECTION 14, T4N-R3E, CONWAY TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN.
SET A 1 1/4" X 36" STEEL PIPE WITH LIVINGSTON COUNTY REMON BRASS CAP #35999 IN PLACE OF THE EXISTING IRON.

S10°E	SP & LIV. COUNTY REMON. TAG ON THE EAST SIDE OF A 18" MAPLE	7.38'
S45°E	SP & LIV. COUNTY REMON. TAG ON THE NORTH SIDE OF A 17" MAPLE	12.48'
N60°E	SP & LIV. COUNTY REMON. TAG ON THE NORTH SIDE OF A 12" CHERRY	35.46'
N10°W	SP & LIV. COUNTY REMON. TAG ON THE EAST SIDE OF A 9" MAPLE	15.63'

Signed by

Date JULY 20, 2000

Surveyor's Michigan License No. 35999



PA. 345 1980, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2-16-2000 CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 28 1977

REVISED MAY 14, 1975

REVISED JAN. 1983

REVISED OCT., 1995