

**MACKINAC COUNTY REMONUMENTATION CORNER**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac  
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 40N R 04W  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

P.C.C. 19

Between M 1/3 &

N 1/3 PC 19

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

#23

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**RECEIVED & FILED**  
DEPT. OF LAND & MINES  
MICHIGAN DEEDS

DEC 11 1995

AM \_\_\_\_\_ PM \_\_\_\_\_  
7/8/95 11:11:11 11/11/95

Register of Deeds Stamp & File Number

I, Neil E. Hill, in a field survey on NOVEMBER 17, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

See sketch on reverse of P.C.C. 18

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1" pipe set by Charlevoix Engineering & Abstract.

Distance checks with record

Accepted corner location.


9" Balsam South 1.43'

14" Cedar N25W 18.50'

6" Balsam N30E 12.60'

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY BOARD AS THE  
OFFICIAL CORNER UNDER P.A.  
245 OF 1980 AT A MEETING  
HELD ON 9-18-95

James H. Granger



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 3/4" pipe, 36" long. Replaced with 5/8" re-rod std. county remonumentation corner.

12" Tw. Maple S40W 9.53'

S09-04-01E 1113.20 feet to SW Cor. PC 19

3" Cedar S20W 9.07'

N09-04-01W 556.60 feet to NW Cor. PC 19

6" Maple N70W 12.65'

6" Maple N35W 11.70'

Signed by Neil E. Hill P.S.

Date NOVEMBER 17, 1995

Surveyor's Michigan License No. 27447