## MAR 2 0 2000

## SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

## **Mackinac County Remonumentation Corner**

Mackinac County Located in: Corner Code # Public Land Survey T42N R01W WCMC G/H-11 Т R Т R #004 R T 2. Property Controlling S Т R in Section S T R 3. Miscellaneous S Т R Property in Sec.

EIVED & FILED DIANE FRANKOVICH CKINAC COUNTY REGISTER OF DEEDS

FEB 2 5 2000

PAA AM 71819110111112111213141516

> C 1) F

2 3 4

5 6

8

9

.0

11

12

13

Register of Deeds Stamp & File Number £

G Н

25

36

Lot No.


For corners in

. Recorded Plat

5. Private Claims

i, Neil E. Hill, in a field survey on 12-20-99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



1845 GLO Notes J Mullett

8" Birch

N 17 W

35 lks

1953 C E Smith

Recorded the "Roach Plat", shows corner location, no witnesses listed

1965 T L Jackson

8" Cedar 6" Cedar N 40 E S 80 E

9.75 24.45

Circuit Court Decree File No 1949 dated Nov 1961

Recorded Liber 173 Page 439, to reset the corner location

Notes large dolimite boulder adjacent to corner location

Book 1 Page 314

Was ordered by a

1981 Sherman Chamerlain - Charleviox A & E Shows location of corner on survey for Jack Law No witnesses listed

No Subsequent Information

SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING 11-05-00 HELD ON

ACCEPTED BY THE MACKINAC COUNTY

عثلا قي سالمبقلا

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 Fd no evidence of original or subsequent corners

Large dolimite boulder has been pushed into lake

Fd witness nail N 40 E in base of cedar, approx 2' under sand, and found other witness nail S 80 E

Reset corner from witness nails

Set 1/2 rod with 4" Alum. remonumentation cap

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" rod with 4" Alum. remonumentation cap

Corner is in a marsh area

10" Cedar N 40 E 9.75 8" Cedar S 80 E 24.45 Pipe in Conc N 35 W 52.24 Pipe N 50 W 122,67'

TO LINE Bearings are compass bearings, corrected for declination, all distances are to a double- head nail in the side of the witness object unless otherwise noted.

esle

January 21 2000

₹ MiC,

Land

Buryeyot

Na

2744

Date

Surveyor's Michigan License No. 27447