

MACKINAC COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mackinac  
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 42N R 6W

F-7

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECEIVED & FILED  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

NOV - 7 1995

AM

PM

7|8|9|10|11|12|1|2|3|4|5|6



Register of Deeds Stamp & File Number

I, James H. Granger, in a field survey on October 4, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1845 Original Survey set wood post 4"beech N41°W 7 lks. 8"maple S79°W 23 lks.  
H.-Brevoort

1915 D. Brotherton

1963 DNR-Billy Buckler #8887 fd iron drift pin

1975 Lawrence Feindt #21566 set "t" iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Worth Road reconstructed. Ex. "T" iron and witnesses by Northwoods Inc. prior to construction. Fd. "T" iron inside monument box.

SURVEY &  
REMONUMENTATION

DEC 01 1995

COMMISSION


ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 9-16-95

*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rebar with remonumentation cap inside monument box.

1/2" iron	N45°W	57.45'
tw. 8"birch	N65°E	143.89' fd tag
11"pine	S56°E	122.61' fd tag
tw. 8"oak	S61°W	101.10' fd tag



Signed by *James H. Granger*

Date 10/27/95

Surveyor's Michigan License No. 16041

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

D-0363