

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>20</u> T <u>43N</u> R <u>10W</u>	<u>D8</u>
	S <u>20</u> T <u>43N</u> R <u>10W</u>	<u>3</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 3 09/24/2009 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D8) Center of Section 20. Established by J.P.Smallwood RLS in 1980. Set 1/2" copper clad rod with  
cap. 6" Quad Cedar S68E 47.34', 12" Spruce S34E 21.21', 9" W.Birch S28W 41.06', 10" Cedar N67E  
61.97'.

(3-Sec. 20) North 1/16 corner between Sections 19 and 20. 1980 - Established by Billy D. Buckler RLS  
midway between Section and 1/4 corners. Set 1" pipe with 4" aluminum cap. 14" Twin Maples S10W  
9.7', 12" R.Maple N85W 45.6', 12" R.Maple N52E 54.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D8) Recovered the 1980 monument in good condition and at record bearing and distance from the  
remaining BT Cedar N67E 61.97'. The other 1980 BTs are now gone. Found the monument to be 0.6'  
South and 1.2' East of the intersection of 1/4 lines of Section 20 and accepted same as a careful and  
faithful establishment of the position of the corner. The monument is buried in the grassy road edge  
in line with road to west and west shoulder of road to north.

(3-Sec. 20) Found the 1980 monument in good condition, substantially at the record position, and at  
record bearing and distance from all three 1980 BTs, found in good condition. Accepted same as a  
careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D8) Fd. 1/2" copper clad rod with cap.  
Set measuring nail with MDNR tag in the side of:  
P.pole EN4 53 4 N54E 56.2'  
10" Cedar S22W 59.7' mrkd "CS BT"  
7" Maple N85E 48.12' do  
Fd MDOT nail in 1980 BT:  
16" Cedar N71E 61.97'  
Bearings are magnetic.

(3) Fd. 1"ID I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
13" twin Maple S10W 10.64' mrkd "N1/16"  
17" R.Maple N81W 45.95' do  
14" R.Maple N55E 55.15' do  
9" Spruce S79W 4.8' mrkd "N1/16 BT"  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/13/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

