

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 10W

85

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Aug 14 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(B5) Quarter corner common to Sections 7-18. 1849: Established by Wm. Ives: East corrected [between Sections 7 & 18]...39.10 Set qr section post. Beech 12 S5W 07, Beech 7 N32E 30...79.10 Section corner. 1969: monumented by Billy D. Buckler, RLS: "This corner placed on line and by single proportionate measure bet. two Section corners. Found no evidence of original corners. Set Wood post. 13" Soft Maple N13W 29.2', 14" Hard Maple S35W 29.1', 14" Hard Maple S75E 19.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B5) The original post and accessories were not recovered. Found the 1969 post, fallen over, at record bearing and distance from the 1969 witnesses, the H.Maple SW now a stump, others in good condition. Determined that the post was placed S20E 12.8' from the position intended in 1969 and I did not accept this position for the corner. Reestablished the corner on a line of mean true bearing between adjacent Section corners, 40.00 chains, proportionate to the original record, west of C5. This position is 2642.40' west of C5 and 2582.93' East of A5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B5) Set 1"IDx36" I.pipe with 4" alum.

MDNR cap. Blazed, scribed, and set

measuring nails in:

16" Maple N4E 17.3' "1/4S" *

20" Maple S50E 29.4' do *

20" Maple S27E 18.8' "1/4S N8T"

6" Maple S85W 24.3' do

Bearings are magnetic. Distances are to

nail with tag. * denotes 1969 witness

tree with new markings made this date.

Signed by Stephan J. Szyszkoski

Surveyor's Michigan License No. 33986

Date 10/14/02

