

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Mackinac	Located In:	Corner Code #
(County)		
1. Public Land Survey	T R	
	T R	
	T R	
	S 32 T 44N R 11W	D12
2. Property Controlling in Section	S 32 T 44N R 11W	9
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on June 14, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
(D12) Center of Section 32. Not established in the original survey. 1979 - Established by Billy D. Buckler RLS at the intersection of lines connecting opposite quarter corners. Set 1" pipe with 4" aluminum cap. 4" Cedar S80E 47.8', 8" W.Pine S02W 98.2'. Corner lies in NE corner of old clearing and 16' South of old grade.  
(9-Sec. 32) East 1/16 corner, Section 32. Not established in the original survey. 1979 - Established by Billy D. Buckler RLS midway between Quarter corner and Center of Section 32. Set 1" pipe with 4" aluminum cap. 14" Cedar S87W 27.2', 6" Cedar S13W 38.1', 8" S.Maple N82E 9.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(D12) Recovered the 1979 monument, the upper portion bent over during road construction. Recovered the visibly undisturbed base of the monument and installed a new monument at that location. Removed the 1979 monument. The 1979 BT Cedar is now a stump. The BT W.Pine is in good condition. Both were found at substantial record bearing and distance.

(9-Sec. 32) Found the 1979 monument in good condition and at record bearing and distance from the BT Maple N82E, in good condition. The two Cedar BTs are gone. Left the monument in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(D12) Set 1"IDx36" I.pipe with yellow plastic cap stamped "MICH DNR LS 33986". Set measuring nails with yellow plastic tags in:  
29" W.Pine S05W 97.6' mrkd "CS" (1979 BT)  
18" Spruce S41W 35.9' mrkd "CS NBT"  
6" Spruce N27E 41.65' do  
6" Balsam S72E 57.6' do  
Bearings are magnetic. Distances are to nail with tag in the side of tree.  
(9-Sec. 32) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails with MDNR tags in:  
14" Maple N83E 9.8' mrkd "E1/16 BT" (1979 BT)  
11" Maple S80W 4.42' do  
10" Maple N17E 17.07' do  
11" Maple S12W 19.05' do  
Bearings are magnetic. Distances are to nail with tag in the side of tree.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski Date 9/18/07

Surveyor's Michigan License No. 33986