

FILED

DEC 23 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

entered

For corners in

MANISTEE

(County)

Located In:

Corner Code #

REGISTER'S OFFICE

MANISTEE COUNTY

98-767 at 3:00pm
JUL 17 1998

Seborah Six
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey

T 21N R 16W

D-13

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous S

T R

Property in Sec.

S T R

4. Lot No. Recorded Plat

5. Private Claims

I, Richard L. Hays, in a field survey on April 1998

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SOUTH QUARTER CORNER OF SECTION 32, T21N-R16W

1838: G.L.O. Survey by John Brink Set post.

11" Y. Pine N-67°-E 31 Lks(1)

7" B. Oak N-30 1/2°-W 11 Lks(2)

1939: M.H. Stickney Book A, Page 72

Iron Pipe No Witnesses

6" Post 4.5' High(3)

1990: Stanley H. Shackelford L.C.R.C 90-178

10" Oak N-42°-W 63.43' (4)

5" Oak N-10°-E 53.58' (5)

10" Oak N-57°-E 60.07' (6)

Post West 1.64' (7)

1" Pipe N-57°-E 38.70' (8)

1982: Robert Griffin Survey Set Rebar

10" Oak N-42°-W 63.43' (4)

5" Oak N-10°-E 53.58' (5)

10" Oak N-57°-E 60.07' (6)

Post West 1.64' (7)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SOUTH QUARTER CORNER OF SECTION 32, T21N-R16W

APRIL 1998: Found Capped 1/2" Iron Rod #13584. Condition of the witnesses are as follows:

11" Y. Pine N-67°-E 31 Lks(1) GONE

7" B. Oak N-30 1/2°-W 11 Lks(2) GONE

6" Post 4.5' High (3) GONE

10" Oak N-42°-W 63.43' (4) FOUND Dock Spike

5" Oak N-10°-E 53.58' (5) FOUND Dock Spike

10" Oak N-57°-E 60.07' (6) FOUND Dock Spike

Post West 1.64' (7) FOUND Nail

3/4" (1") Pipe N-57°-E 38.70' (8) FOUND

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SOUTH QUARTER CORNER OF SECTION 32, T21N-R16W

APRIL 1998: Accepted 1/2" Iron Rod and replaced with a MANISTEE COUNTY MONUMENT as the best available evidence of the position of the Corner.

14" Oak N-42°-W 63.46' (4) Dock Spike

6" Trip. Black Oak S-31°-E 35.36' 60 Penny Nail

7" White Oak N-10°-E 53.60' (5) Dock Spike

12" Black Oak N-57°-E 60.16' (6) Dock Spike

5" Red Pine S-46°-W 31.88' 60 Penny Nail

Post West 1.64' (7)


Corner D-13

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: JUL 7 1998

Anthony M. Slawinski

Signed by

Surveyor's Michigan License No. 25847



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1983