

SURVEY & REMONUMENTATION

DEC 09 1999

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**
MANISTEE
(County)

Located In:

Corner Code #

#002

1. Public Land Survey

T 21N R 14W

C-13 mc

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTER'S OFFICE
MANISTEE COUNTY

79-288 at 11:50AM

SEP - 9 1999

Deborah Six
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kenneth L. Ross, in a field survey on June 29 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13 mc Meander Corner on the East Shore of Lake of the Woods, T21N, R14W.

1838, John Brink G.L.O. boundary survey

Set post at 78.50 chs.

#1 White Pine 6" N 23 W 36 lks. (23.76')

#2 White Pine 7" S 41 E 34 lks (22.44')

No Date, Ted Weinert, RLS #19846

Set 1 1/4" Iron Pipe and Cedar post

at G.L.O distance from 1/4 cor.

1992, Norman Caldwell, RLS #12018

Found 1 1/4" Iron Pipe by Weinert and replaced with a 2' x 5/8" Re-rod with Alum. cap stamped identify the corner.

#3 Maple 6" S 88 E 29.31'

#4 Black Ash 3" S 36 E 9.29'

#5 Cedar 10" N 46 E 12.12'

#6 Carsonite Post West .30'

L 92 Page 438

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 mc Meander Corner on the East Shore of Lake of the Woods, T21N, R14W.

On June 29, 1999, Kevin Pritchard (survey tech.) and I found 1 1/4" Iron Pipe with 5/8" Re-Rod, 3" aluminum cap, Stamped M.C. T21N, R14W. Iron is 40 feet East of East shore line. I found no evidence to dispute this location for the corner.

Condition of record witnesses are as follows: #1 Gone #2 Gone #3 Found in good condition

#4 Found in good condition #5 Found in good condition #6 Found in good condition

Corner _____ ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: Anthony M. Hauke

SEP 07 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 mc Meander Corner on the East Shore of Lake of the Woods, T21N, R14W.

I accepted 5/8" Re-Rod with Aluminum Cap inside 1 1/4" Iron Pipe as substantial marker for the corner and is accepted as a careful and faithful perpetuation of the original corner.

Ext. BT #3 Maple 10" S 88 E 29.81' (fd. 60d spike in South side of tree)

Ext. BT #4 Black Ash 6" S 36 E 9.29' (fd. 16d spike in SW side of tree)


Ext. BT #5 Cedar 12" N 46 E 12.12" (fd. 60d spike in NW side of tree)

Ext. BT #6 Carsonite Post .30 feet West

Signed by [Signature]

Date 9-7-99

Surveyor's Michigan License No. 17634



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JUL 28, 1971
REVISED MAY 14, 1999

ADAPTED FOR WORD PROCESSING MARCH, 1993