

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MANISTEE

(County)

Located in:

Corner Code -#

1. Public Land Survey

T 22N R 16W

E-3

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

REGISTER'S OFFICE
MANISTEE COUNTY

95-348 at 1:20pm

SEP - 7 1995

Rebecca Six, Dep.
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, John Schulke, in a field survey on July 12th, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
In 1839, J. Brink (Deputy Surveyor) set a wooden post with the following corner references:

1. Maple 12" N63°E 7 lks.
2. Beech 14" S30°W 62 lks.

In 1848, B.O. Risdon used corner to establish the 1/4 corner between Sections 8 and 9, South 40.15 chains (2649.9 ft.).

In 1904, Harrison Knight set stone (see Book B, pages 184 & 185 in the Manistee County Register of Deed's Office).

3. W Pine Stump 20" S88°W 71 lks.
4. W Pine stump 24" S46 1/2°W 78 1/2 lks.

Undated Manistee Co. Rd. Commission record indicates an iron pipe at the corner. The following corner references: 5. Fence post West 33.08 ft.
6. popple 5" NW 45.03 ft.
7. popple 10" SE 67.44 ft.

In 1976, T. O'Brian set 3/8" iron bar with a cap (#RLS 21274) from witness tag (see LCRC #77-20 filed in the Manistee Co. Register of Deed's Office).

8. Maple 12" N38°W 43.65 ft.
9. W Pine 6" S85°W 44.0 ft.
10. Maple 6" S47°E 34.15 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In 1994, I recovered O'Brian 3/8" iron while surveying in Section 9.

In 1995, I recovered O'Brian 3/8" iron in the center of Faulk Road on top of hill. Road cut to the West and road fill to the East. (11.) Found capped iron by RLS #12531 S84°E a distance of 32.99 feet. Found the following corner references 5, 8, 9 and 10. Note: #10 was found to be a White Ash. Fences running East and West. Corner fence post N62°E a distance of 35.1 feet (fences runs North and East of the corner post). References #1, 2, 3, 4, 6 and 7 were not recovered. Distances to the following corners:

- E-2 (East 1/4 corner of Section 5) 2625.86 ft. by Jenema
F-3 (South 1/4 corner of Sec. 4) 2623.20 ft. by Schulke & Jenema
E-4 (East 1/4 corner of Section 8) 2649.78 ft. by Schulke
D-3 (South 1/4 corner of Sec. 5) 2631.62 ft. by O'Brian

Corner E-3 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990 as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review SEP 5 1995


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Considering the position of the 3/8" iron to be the faithful perpetuated location of the GLO corner, I replaced the 3/8" iron with a 2" dia. X30" galvanized pipe monument with brass cap stamped to identify the corner. The monument is 1 foot below the surface of the road. The following corner references:

5. Fence post N84°W 31.5 ft.
8. Twin R Maple (S Trunk) 12" N32°W 43.75 ft.
9. W Pine 7" N86°W 43.98 ft.
10. W. Ash 10" S43°E 34.44 ft.
11. capped iron (RLS #12531) S84°E 32.99 ft.

New corner references:

12. W. Ash 4" N68°E 32.79 ft.

NOTE: 60-D spike placed in references #8, 9, 10 and 12.



Signed by

John C. Schulke

Date July 31, 1995

Surveyor's Michigan License No. RLS#30894