

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>23</u> N. <u>14</u> R. <u>14</u> W.		<u>K-4; M-1; M-2; M-3</u>
2. PROPERTY CONTROLL- ING IN SECTION_____ ,T. _____ N. _____ E. S., R. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION_____ ,T. _____ N. _____ E. S., R. _____ W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 12-26 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found, etc.

**M-2** Recovered concrete monument per Manchester survey in 1928.

**M-3** Recovered W. E. Manchester corner of record, 1928.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**K-4** Reestablished corner equidistant and on line between Sec. corners N & S. Corner falls in line with Approx. center of large drainage ditch to S & E. Checked with man who constructed the ditch years ago and he said they tore out the 1/4 corner while excavating the ditch to the S & E from the 1/4 corner. Corner position also fits 1/8 line fence 1/4 mile W & N-S Rd. 1/2 mile W.

**M-1** Recovered B. Spike in approx. center of E-W B. top rd which fits Manchester survey of Sep. 1 in 1928

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4	M-1	M-2
Set DNR Mon & Ced gd post	Fd 3/4" Sq. Boat Spike	Fd. 4" sq con mon. Set Ced
14" Maple S80W 26.1'	Ctr old RR Grade NE-SW Due E 7'	gd post w/loc tag
10" Maple S52E 29.0'	12" Maple N45W 66.2'	18" Ced stp. S 6W 32.7'
5" Maple S74E 31.6'	5" Y. Birch tw N30W 42.3'	7" Maple S42W 36.8'
	10" B. Cherry N56E 113.2'	6" Maple N 7W 40.1'
	Set Ced. Post W/loc tag	8" Maple N62E 29.8'
	Due N 33'	
(Fd 4"x4" Cedar Stk.		
(Added DNR mon & Ced gd post		
(8" Y. Birch S50W 11.1'		
(8" Cedar N53W 28.2'		
(6" Cedar S70E 20.4'		


SIGNED BY Carl F. Roser DATE 6-15-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_