

SURVEY & REMONUMENTATION

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners In: Located In: Corner Code #
Mason County

1. Public Land Survey T 17N R 18W
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

L-10 *Seg. 2*

FILED
AT 7:14 O'CLOCK P. M
JAN 9 2000
MARGARET KOLASKI ELLIOTT
MASON COUNTY
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Kenneth L. Ross in a field survey on September 18, 2000, Do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Center 1/4 corner of section 25, T17N, R18W

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not set by GLO

Stephens RLS 7318 fd. corner.
Jobs are reference in Stephens notes Book 1 Page 10, Jan. 1953 and Book 5 page 5, Sept. 4, 1954.

Ross RLS 17634
Unrecorded surveys, 1994, and 1995.
L 501 P 1758
Fd. 1/4" x 1.4" above ground SE cor.
Govt. Lot 1, AKA as Center 1/4 corner.
10" Hemlock S24W 18.79' #1
12" Hemlock S46E 35.97' #2
10" Hemlock S75W 44.24' #3
10" Ash N30W 32.61' #4
Fd. trace of fence north and fence that was down to the west

Ross RLS 17634
In October, 1998 pursuant to judgment on court order 97-95-CZ in conjunction with the amended plat I replaced the 1/4" x 1 1/2" pipe with a concrete monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a concrete monument with a trace of fence North and East and visible remains of a fence to the West.

Condition of the accessories is as follows: 1, 2, 3, and 4 are good condition.

I found no reason to dispute the location of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


I replaced the concrete monument with a Harrison monument stamped "Mason County Monument PLS 17634". I accepted this as a careful and faithful establishment of the position of the corner.

10" Hemlock S24W 18.79' #1 ex. 60d nail
Hemlock S46E 35.97' #2 ex. 60d nail
10" Hemlock S75W 44.24' #3 ex. 60d nail
10" Ash N30W 32.61' #4 ex. 60d nail

Signed by *Kenneth L. Ross* Date 10-09-2000

Surveyor's Michigan License No. 17634

Approved by Peer Review Group on 10-09-2000
Kenneth L. Ross, County Representative *Kenneth L. Ross*



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28,

1971
REVISED MAY 14, 1978
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993