

DEC 18 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mason

(County)

Located In:

Corner Code #

1. Public Land Survey

T 19N R 18W

H-9

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Section

S T R

FILED	
AT 10:41	O'CLOCK a M
OCT 19 1995	
MARY GOLDEN KOLASKI MASON COUNTY REGISTER OF DEEDS	
Register of Deeds Stamp & File Number	

4. Lot No. , Recorded Plat

5. Private Claims

I, Richard Hays, in a field survey on September, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

H-9 SECTION CORNER COMMON TO SECTIONS 22 AND 27, T19N-R18W

G.L.O.:1838 Sibley Survey

12" Pine S-18°-E 3 Lks (1)

8" Beech N-66°-W 9 Lks (2)

MASON COUNTY ROAD COMMISSION SURVEY

Found 1-1/4" Pipe

8" Maple S-15°-E 92.8' (3)

Power Pole S-35°-W 83.4' (4)

1901:Robert O. Towns Survey

Book 4, Page 46, Set Iron

Pipe from GLO Witnesses

1973-1974:Ross Survey #17634

Act 132, Liber 313, Page 220

Found Lunde Concrete Monument-NO WITNESSES

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-9 SECTION CORNER COMMON TO SECTIONS 22 AND 27, T19N-R18W

September 1995:Found Concrete Monument 56' North of Centerline of Dewey Rd.  
Found no other evidence to dispute this location. Condition of the  
Recorded Witnesses are as follows:

12" Pine	S-18°-E	3 Lks (1)	GONE
8" Beech	N-66°-W	9 Lks (2)	GONE
8" Maple	S-15°-E	92.8' (3)	FOUND
Power Pole	S-35°-W	83.4' (4)	GONE


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-9 SECTION CORNER COMMON TO SECTIONS 22 AND 27, T19N-R18W

1995:Accepted 4" x 36" Concrete Monument with cap as a careful and faithful perpetuation of the position of the Original Corner.

Power Pole	S-45°-W	84.40'
20" Maple	S-17°-E	92.82' (3)
11" B. Oak	N-27°-W	23.46'
16" W. Pine	N-26°-E	48.72'

Centerline of Dewey Road South 56'



Signed by

*Richard Hays*

Date October 17, 1995

Surveyor's Michigan License No. 25847

Peer Group Reviewed  
and Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER

3 PAGE 328

Date: *10-18-95*  
*Kenneth L. Rose*  
Mason County Surveyor