

SURVEY &  
REMONUMENTATION

OCT 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MASON Located In: Corner Code #  
(County)

1. Public Land Survey T 20N R 15W I-10  
T    R     
T    R     
T    R   

2. Property Controlling S    T    R     
in Section S    T    R   

3. Miscellaneous S    T    R     
Property in Sec. S    T    R   

FILED  
AT 11:55 O'CLOCK a M  
AUG 14 1996  
MARY GOLDEN KOLASKI  
MASON COUNTY  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No.   , Recorded Plat     
5. Private Claims   

I, Sammy S. Barnett, in a field survey on July 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10 1/4 Corner for Section 26 and 27, T20N, R15W.

1839, John Brink, C.L.O.

Set Wood Post

#1 W. Oak 10" S 26° W 151ks.(9.90')

#2 W. Oak 11" N 85° E 251ks.(16.50')

1976, Ken Ross, #17634

Set 1/2" Re-rod @ single proportional method

#3 W. Oak 24" N07°W 79.94'

#4 Jack Pine 16" N10°E 31.87'

#5 Jack Pine 16" N70°E 43.35'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 1/4 Corner for Sections 26 and 27, T20N, R15W.

On July 23, I found 1/2" Re-rod with RLS cap #17634, Ross, corner is 600 feet + - East of Trail Road. I found no evidence to dispute this corner.

Condition of recorded witnesses are;

#1 Gone

#2 Gone

#3 Found in good condition

#4 Found in good condition

#5 Found in good condition

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 1/4 corner for Sections 26 and 27, T20N, R15W.

I replaced 1/2" Re-rod, in the exact location, with a Standard Mason County Monument, flush with the ground, and is accepted as a careful and faithful reestablishment of the position of the original corner.

(ext. BT #3) White Oak 24" N 07° W 79.94'(60d spike in SW side of tree)

(ext. BT #4) Jack Pine 17" N 10° E 31.87'(60d spike in SW side of tree)


(ext. BT #5) Jack Pine 17" N 70° E 43.35'(60d spike in NW side of tree)

Jack Pine 16" N 40° W 22.22'(60d spike in SW side of tree)

Signed by Sammy S. Barnett

Surveyor's Michigan License No. 16923

Date 8-12-96



Peer Group Reviewed  
and Approved

Date: 8-13-96

Kenneth L. Ross  
Mason County Surveyor

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995