

SURVEY &
REMONUMENTATION
MECOSTA COUNTY REMONUMENTATION PROGRAM

CORNER APPROVED BY PEER GROUP ON MAY 18, 1995

APR 04 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mecosta
(County)

Located In:

Corner Code #

Joanne Brown
Register of Deeds
Mecosta County

'95 NOV -2 A11:13

1. Public Land Survey Sec 15 T 15N R 7W H-7
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, James J. Keller, in a field survey on February 1 19 95,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

July 20 1838, Noah Brookfield, Deputy surveyor, GLO Notes "Set 1/4 post in tree line" Pine 30" S76°W 18 Links; Beech
10" N48°E 27 Links (Book 1 Page 96)
1895-96 Lyman W. June, County Surveyor, "12" Birch is corner", Pine Stump S76°W 18 Links = Old Bearing tree, Black Oak
20" N75°E 78 Links
1900 Lyman W. June, County Surveyor, "Tile corner"
1976 Herbert L. Fluharty #18223, (L10 Pg.328) Found 5/8" Iron and set cap", Road sign S42°W 49.33', 8" Poplar S82°E
87.53', 8" White Pine N73°W 25.74'
Feb. 2 1979, Thomas J. Mueller, #25861 (L10 Pg.779) (LCRC L1-Pg.474) "Found 5/8" Iron With RLS. cap" Road sign S42°W
49.33', 8" Poplar S82°E 87.53', 8" White Pine N73°W 25.74'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

February 1, 1995 James J. Keller #10693, Found 5/8" rebar & Cap; Dug for Junes tile but could not find it. Accepted
location and set remonumentation monument 3" deep in place of rebar.
Set 60d and tag North East side 18" White Pine N71°W 25.35'
Set 60d and tag East side 8" Red Pine N12°E 43.33'
Set 60d and tag South side 14" Wild Cherry S82°E 64.12'
Set 60d and tag East side 18" White Pine S30°E 71.29'


APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James J. Knapp
CHAIRMAN
DATE May 18, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument and is accepted as a careful and faithful perpetuation of the position of the original
corner.

Set 60d and tag North East side 18" White Pine N71°W 25.35'
Set 60d and tag East side 8" Red Pine N12°E 43.33'
Set 60d and tag South side 14" Wild Cherry S82°E 64.12'
Set 60d and tag East side 18" White Pine S30°E 71.29'



Signed by James J. Keller Date 27 June 1995
Surveyor's Michigan License No. 10693

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993