

L. C00004, P. 00301

9/11/18

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean Field Survey Date: 1/30/18
For corner(s) in: Midland County

Original Public Land Survey Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Controlling Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Corner			Corner Code
S	10	T 14N R 2W	14
S		T	R
S		T	R
S		T	R

Protracted Public Land Survey Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2	6		5		4		3		2		1			2
3														3
4	7		8		9		10		11		12			4
5														5
6	18		17		16		15		14		13			6
7														7
8	19		20		21		22		23		24			8
9														9
10	30		29		28		27		26		25			10
11														11
12	31		32		33		34		35		36			12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

14 -S 1/16 corner common to sections 10 and 11, T14N R2W
1900's - S. Carroll Drain notes – F.T. Gibbs "Cross line between section 10 & 11, 22 chs. north of south line of said section"
1983 – Rec. Sur. L.3, P.409 – J. L. Jones (PS # 19838) – Set ½" rod


Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

- 14-** S 1/16 corner, common to sections 10 and 11, T14N, R2W.
Fnd 1/2" x 18" rebar w/ broken cap per Jones in remains N-S fence. CL. of old bridge over S. Br. Carrol Creek Drain is N5°W 97'. 1/2" CIR accepted as the best available evidence of the position of the corner.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

- 14** - S 1/16 corner common to sections 10 and 11, T14N, R2W.
Replaced 1/2" CIR w/ stamped 2" Aluminum Cap on 5/8"x 34" long iron rebar.
N4°E 26.27' to set N&T in W. side of 5" Oak
N45°E 34.38' to set N&T in NW side of 6" Oak
N69°E 31.61' to set N&T in S. side of 10" Oak
S31°W 31.12' to NW Cor. wood shed
Set Blue Composite Post w/ Loc. Tag 1' NE




Craig W. McVean

9/10/2018
Date

Professional Surveyor's License No.: 39088

Prepared By:
Craig W. McVean
Michigan Dept. of Natural Resources
8015 Mackinaw Trail
Cadillac, Michigan 49601