

# Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean

Field Survey Date: September 20, 2016

For corner(s) in: Midland County

## Original Public Land Survey Corner

## Corner Code

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

## Property Controlling Corner

## Corner Code

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

## Property Corner

## Corner Code

S 27 T 16N R 1W 13  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

## Protracted Public Land Survey Corner

## Corner Code

S 27 T 16N R 1W H10  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9														9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

## Part A: Corner History

**H10** – Center ¼ corner Section 27, T16N, R1W-  
 -No history

**13** – SE 1/16 corner Section 27, T16N, R1W-  
 -No history

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

H10 – Center ¼ corner Section 27, T16N, R1W.

Set stamped 2" aluminum cap on 5/8" x 34" long rebar per standard BLM procedure. N40°W 20.5' to found steel fence post with cable to north and west.

13 – SE 1/16 corner Section 27, T16N, R1W.

Set stamped 2" aluminum cap on 5/8" x 34" long rebar per standard BLM procedure. North end of row of wood posts to the south is 21' west.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

H10 – Center ¼ corner Section 27, T16N, R1W.

Stamped 2" aluminum cap on 5/8" x 34" long rebar. Set blue composite post with location tag 1' southeast


N53°E 14.35' to set nail & tag in southeast side 10" Oak  
N75°W 39.88' to set nail & tag in south side 10" Oak  
S18°W 25.19' to set nail & tag in west side 3" Oak  
S32°E 37.81' to set nail & tag in northeast side 3" Oak

13 - SE 1/16 corner Section 27, T16N, R1W


Stamped 2" aluminum cap on 5/8" x 34" long rebar. Set blue composite post with location tag 1' west

S65°W 44.63' to set nail & tag in north side 9" R. Maple  
S07°E 27.46' to set nail & tag in east side 7" W. Oak  
S86°E 38.05' to set nail & tag in north side 3" W. Pine  
N18°E 36.61' to set nail & tag in east 5" Oak





Craig W. McVean



Date

Professional Surveyor's License No.: 39088

Prepared By:  
Craig W. McVean  
Michigan Dept. of Natural Resources  
8015 Mackinaw Trail  
Cadillac, Michigan 49601