

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette

(County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 29W J11  
T R  
T R  
T R  
T R

2. Property Controlling  
in Section

S 36 T 45N R 29W 6  
S T R  
S T R  
S T R

3. Miscellaneous  
Property in Sec.

4. Lot No. , Recorded Plat

5. Private Claims

J11 Dec 11 2002  
6 Dec 09 2002

I, Stephan J. Szyszkoski, in a field survey on         , 20     do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J11) Quarter corner common to Sections 26-35. 1959-- Remonumented in the original position by B.D.Buckler. 1" iron pipe with 4" brass cap. 12" W.Pine N48E 41 links, 15" Y.Pine S48W 53 links. 1983 - The 1959 monument was recovered by D.E.Erickson, rewitnessed, and rerecorded: Found 1" iron pipe with brass cap. Witnessed by 6" spikes in: 18" W.Pine N55E 27.29', PK nail in 5" Maple S65E 23.52', 18" R.Pine S50W 35.18', 10" R.Pine N45W 5.37'.  
(6-Sec. 36) Northeast 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J11) Found the 1959 monument in good condition and at substantial record bearing and distance from the 1983 accessories. The W.Pine NE is now dead but standing. The other three witnesses have overgrown blazes. One blaze on the R.Pine SW has been opened up by someone.  
(6-Sec. 36) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the position thus established, I found an iron pin set by an unknown party S40W 14' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J11) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nail in: 4" R.Pine S28E 18.8' 1/4S NBT  
The 1983 witnesses:  
22" R.Pine S53W 35.2' nail/old blaze  
8" twin Maple S62E 23.5' do  
15" R.Pine N42W 5.4' do  
A sq'd cedar post is adjacent. Bearings are magnetic. Distances are to nail or overgrowth seam covering nail.  
(6) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
6" dbl B.Spruce N08W 70.10' 1/16S BT  
2" B.Spruce S77E 5.39' do  
20" R.Pine S16E 105.75' do  
10" dbl R.Pine S81W 36.95' do  
Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/19/02