

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 30W T R T R	B1 (GCDB 140700)
2. Property Controlling in Section	S 6 T 45N R 30W S T R S T R	14 (GCDB 200620)
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/11/16 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B1) Quarter corner common to Section 6 T45N-R30W and Section 31 T46N-R30W. 1961 - Remonumented by
Neal Sperhake RLS at the position of an iron pipe which he found to be 24 links from the position
proportionate to the original record between section corners. Set 1"IDx36" Iron pipe with 4" alum.
Kimberly-Clark Corp. cap. Poplar 3" N13°E 16 links, Balsam 10" S53°E 36 links.

(14-Sec. 6) South 1/16 corner between Sections 5 and 6. Established by Alan Pierce RLS 30097,
presumably during a survey within Section 5, dated 6/15/88, but not noted on the survey drawing as
having been set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B1) Found the 1961 monument in good condition but with cap broken, the center portion still in
intact and readable. The 1961 witnesses were not recovered. A check of the distance A1 to B1 finds
it to be about 5.8' shorter than noted in the Sperhake record. I accept the monument as the best
available evidence of the position of the original corner.

(14-Sec. 6) Found a 1/2" rebar with plastic cap stamped "ECI 30097 44283" with two nearby witness
trees marked with blazes and plastic tags bearing the same information. The 1/2" capped rebar is
substantially midway and on line between 1/4 corner to north and Section corner to south and I
accept same as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B1) Found 1"ID I.pipe with 4" alum. Kimberly-Clark
Corp. cap. Set measuring nail with MDNR tag in the
side of:
5" Balsam N30°E 7.05' mrkd "1/4S NBT"
5" Cherry S29°E 19.65' do
4" Balsam South 10.15' do
12" Poplar N74°W 23.15' do
Set sq'd cedar post adjacent.
E= 7914788.68 N= 172858.92

(14) Found 1/2" capped rebar.
Found measuring nail "ECI 30097 44283" in:
6" Spruce S05°E 32.85' overgrown blazes
11" Spruce S78°W 17.5' do
Set measuring nail with MDNR tag in the side of:
7" Cherry N03°E 37.35' mrkd "1/16S BT"
11" Balsam N17°E 25.05' do
Sq'd cherry post adjacent.
E= 7915549.19 N= 171645.48

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum
Coord. Ref.=NGS PID AA8080: N= 192972.689 m. E= 7925456.741 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 05/19/2016

For the Michigan Department of Natural Resources, Forest Resources Division

