

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 28W	C8
	T 48N R 28W	D7
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File  
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

Jul 10 2007  
I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C8) Quarter corner common to Sections 19 and 20. 1848 - Established by Wells Burt, Deputy Surveyor: Set Tamarack post midway and on line between Section corners 40.00 chains north and south. Spruce 9 S50W 18 links, Spruce 9 N50E 42 links.  
(D7) Quarter corner common to Sections 17 and 20. 1848 - Established by Wells Burt, Deputy Surveyor: Set Maple post midway and on the Section line between Section corners 39.73 chains east and west. Sugar 9 N27E 20 links, Y.Birch 16 S21W 39 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C8) The original post and accessories were not recovered. Found a 2.5" ID iron pipe projecting 1.7 ft. above ground, not of record, and accepted same as the best available evidence of the position of the original corner. The position of the pipe checks well with reestablished Section corner C7 to the north (2641.63' M 2640' R) and checks well for line between monumented corners C13 and C7 (9.1' east of the line).  
(D7) The original post and accessories were not recovered. Found a 2.5" ID iron pipe, projecting 12" above ground, set firm, not of record, and accepted same as the best available evidence of the position of the original corner. The pipe is 8.9' East and 5.0' South of the midpoint position between monumented Section corners 2626.66' west and 2608.76' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C8) Found 2.5" ID I.pipe. Set measuring nails in:	(D7) Found 2.5" ID I.pipe. Set measuring nails in:
6" Cedar S22E 13.1'      mrd "1/4S NBT"	11" Sugar S22W 19.4'      mrd "1/4S NBT"
6" Spruce S14W 14.1'      do	9" twin Sugar S38W 14.9'      do
6" Maple S63W 9.3'      do	4" Sugar S77W 13.5'      do
3" Spruce N89E 3.8'      do	7" Poplar N15W 2.5'      do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.	Fd. treated 4x4 post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 8/14/07

For the Michigan Department of Natural Resources, Office of Land and Facilities