

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 30W T _____ R _____ T _____ R _____	F1 (GCDB 340700)
2. Property Controlling in Section	S 16 T 48N R 30W S _____ T _____ R _____ S _____ T _____ R _____	2 (GCDB 360500)
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 2 08/28/14 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F1) Quarter corner common to Section 4 T48N-R30W and Section 33 T49N-R30W. 1846 - Established by
John Burt, Deputy Surveyor midway and on the Township line between Section corners 40.00 chains east
and west. Spruce 9" for corner. W.Pine 22" N30°W 5 links. Found no subsequent record.

(2-Sec. 16) East 1/16 corner between Sections 9 and 16. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F1) The original corner tree and accessory were not recovered. Found no acceptable evidence of the
position of the original corner on the ground. Reestablished the position for the corner on the
Township line between Section corners 2634.12' east and west.

(2-Sec. 16) Established the position for the corner midway and on the Section line between Quarter
corner 1323.50' west and Section corner 1323.50' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F1) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
The pipe was driven to refusal, about 1 ft. deep,
and made firm in a mound of rock. Set measuring
nail with MDNR tag in the side of:
16" W.Pine N07°E 12.15' mrkd "1/4S NBT"
2" B.Spruce S73°E 17.9' "X X"
4" W.Pine S38°W 14.7' "1/4S NBT"
B.Spruce S80°W 12.2' do
Set sq'd cedar post adjacent.
E= 7918421.251 N= 201639.272

(2) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
The pipe leans slightly NW. The top center of the
cap marks the corner position. Set measuring nail
with MDNR tag in the side of:
7" Balsam N25°E 13.55' mrkd "1/16S BT"
12" W.Pine East 39.5' do
4" Balsam S03°E 3.6' do
14" W.Pine N88°W 18.7' do
E= 7918766.947 N= 198465.076

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID AA8080: N= 198400.952 m. E= 7925456.741 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/12/2014

For the Michigan Department of Natural Resources, Forest Resources Division

