

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 16 T 52N R 29W	13
	S 16 T 52N R 29W	12
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 13 11/08/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(13-Sec. 16) Southeast 1/16 corner, Section 16. Not established in the original survey.

(12-Sec. 16) South 1/16 corner, Section 16. 1994 - Established by G.C.Van Neste PS midway and on a straight line between Quarter corner 1320.24' south and Center of Section 16 1320.24' north. Set 5/8" rebar with plastic cap #27464. 42" Hemlock stump N01E 9.16', 29" Hemlock S30W 21.90', 22" Hemlock S27E 7.84', 18" Hemlock N64W 15.22'. Trees blazed, painted and witnessed with galvanized nail and washer.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 16) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(12-Sec. 16) Found the 1994 monument in good condition and at record bearing and distance from the 1994 witnesses. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 7" Maple S19E 16.3' mrkd "1/16S BT" 9" Maple S42W 9.4' do 8" W.Spruce S75W 19.8' do 8" W.Spruce N17W 29.6' do Set sq'd cedar post adjacent. Bearings are magnetic.

(12) Fd. 5/8" dia. rebar with plastic cap #27464 Found meas. nail with GCVN tag in the side of: 22" Hemlock S25E 7.9' with upper blaze 28" Hemlock S31W 21.9' do 17" Hemlock N61W 15.2' do Set measuring nail with MDNR tag in the side of: 21" Hemlock N23W 25.0' mrkd "1/16S BT" Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 02/02/2011

For the Michigan Department of Natural Resources and Environment, Forest Management Division

