

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 29W	C6
	T 52N R 29W	G7
2. Property Controlling in Section	T R	
	T R	
	T R	
3. Miscellaneous Property in Sec.	T R	
	T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on C6 11/03/2010 G7 11/04/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17-18. 1990 - G.C.Van Neste PS found and accepted a 1 1/4" dia. iron pipe 2638.37' north of Section corner C7, 2615.63' east of Center of Section 18, and 2637.07' west of Center of Section 17.

(G7) Corner common to Sections 15-16-21-22. 1990 - G.C.Van Neste PS found a 1" ID Iron pipe, no cap, on N-S blue paint line, old blazes and witness tag, and barbed wire fence to west, and being 2636.52' east of Quarter corner F7.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) Found a 1 1/4" ID iron pipe, in good condition, 2638.74' north of monumented C7, 2615.72' east of monumented B6 and 2636.97' west of monumented D6. Accepted the monument as the best available evidence of the position of the original corner.

(G7) Found a 1" ID Iron pipe, in good condition, in a small rock mound, with Keweenaw Land Co. location poster facing on 10" Maple N38W 8.9' distant. Distance west to monumented F7 was found to be 2636.76'. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Found 1 1/4" ID Iron pipe.  
Set measuring nail with MDNR tag in the side of:  
8" Cedar N18E 22.5' with old blaze  
8" twin Maple S40E 20.4' mrkd "1/4S NBT"  
6" Maple S21W 27.5' do  
6" Maple N08W 25.65' do  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

(G7) Found 1" ID I.pipe. Set plastic MDNR cap in the pipe and improved the rock mound in which the monument was found.  
Set measuring nail with MDNR tag in the side of:  
10" Maple N38W 8.9' old blaze and poster ind.  
6" Ironwood S88E 6.4' mrkd "S22 NBT"  
12" Hemlock S68E 17.9' do  
9" Sugar S34W 26.7' "S21 NBT"  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 02/02/2011

For the Michigan Department of Natural Resources and Environment, Forest Management Division

