

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Menominee (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____ _____ _____
2. Property Controlling in Section	S 11 T 34N R 29W S 11 T 34N R 29W S _____ T _____ R _____	9 13 _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Jeremy J. Pipp, in a field survey on 4/05/2012AD do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(09) Center-East One-Sixteenth corner of Section 11. Not set in original survey, no  
evidence of subsequent establishment.

(13) Southeast One-Sixteenth corner of Section 11. Not set in original survey, no  
evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(09) Corner position established mid-point and on-line between the Center One-Quarter  
corner and the East One-Quarter corner of Section 11.

(13) Corner position established at the intersection of the South and East One-Sixteenth  
lines of Section 11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


(09) DNR monument  
9" Oak N53E 13.78' (1/16S,BT)  
9" White Pine S60E 22.51' (1/16S,BT)  
11" Oak S33W 10.85' (1/16S,BT)  
6" White Pine N25W 4.93' (1/16S,BT)

All trees are blazed, scribed, and  
painted. Measurements are to nail in  
side of tree, bearings are magnetic.

(13) DNR monument  
14" White Pine N70E 50.46' (1/16S,BT)  
18" Red Pine S54E 25.77' (1/16S,BT)  
18" Oak S39W 38.16' (1/16S,BT)  
18" White Pine N06W 38.44' (1/16S,BT)  
All trees are blazed, scribed, and  
painted. Measurements are to nail in side  
of tree, bearings are magnetic.

Signed by Jeremy J. Pipp  
Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources



Date July 17, 2012

20063

20062

APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995