

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Menominee	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 41N R 26W	E03
	T 41N R 26W	E04
	T R	
2. Property Controlling Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

8/20/2014
Jeremy J. Pipp, in a field survey on 8/20/2014 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E03) Section corner common to Sections 4, 5, 8, and 9. 1852: E.C. Martin, DS. Set section post
witnessed by Fir 10 S34W 21 links (13.86'), Sugar 18 N77E 8 links (5.28'). No evidence of
subsequent establishment.

(E04) Quarter corner common to Sections 8 and 9. 1852: E.C. Martin, DS. Set quarter section post
witnessed by Cedar 18 S45E 24 links (15.84'), Cedar 14 N57W 14 links (9.24'). No evidence of
subsequent establishment.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E03) No evidence of original survey. Corner position reestablished by double proportionate
measurement using existing corners one-half mile North, one & one-half miles East, one & one-half
miles South, and one-half mile West. Area has been severely disturbed by roadway construction
(corner falls on berm +/-12 feet south of roadway). Position is accepted as a careful and faithful
REESTABLISHMENT of the position of the original corner.

(E04) No evidence of original survey. Location has been altered by logging activities; corner falls
15 feet North of skid road in a recent clear cut. Corner position reestablished by single
proportionate measurement between the Northwest corner and the Southwest corner of Section 9.
Position is accepted as a careful and faithful REESTABLISHMENT of the position of the original
corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E03)	DNR monument	(E04)	DNR monument
7" Ironwood	N47E 111.08' (S4,NBT)	3" Poplar	N30E 17.57' (1/4S,NBT)
7" Spruce	S52W 33.45' (S8,NBT)	5" Spruce	S43E 39.10' (1/4S,NBT)
9" Maple	N70W 75.17' (S5,NBT)	3" Poplar	S08W 27.85' (1/4S,NBT)
5" Spruce	N03W 40.46' (S5,NBT)	3" Poplar	N44W 11.98' (1/4S,NBT)
All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic. A Metal sign post was set South 1.5 feet.		All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic. A Metal sign post was set North 1.5 feet.	

Signed by _____ Date August 26, 2014

Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources, Forest Resources Division

20437

20438



Register of Deeds Stamp & File Number												
A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												