

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

for corners in

Menominee Located In: Corner Code #
1. Public Land Survey T 41N R 26W E06
2. Property Controlling n Section S T R
3. Miscellaneous Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

8/13/2014
Jeremy J. Pipp, in a field survey on 8/13/2014 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E06) Quarter corner common to Sections 16 and 17. 1852: E.C. Martin, DS. Set quarter section
post witnessed by Cedar 12 S60E 13 links (8.58'), Cedar 8 N19W 12 links (7.92'). 2014: Found
wood post by unknown persons.

(E07) Section corner common to Sections 16, 17, 20, and 21. 1852: E.C. Martin, DS. Set section
post witnessed by Cedar 18 N32E 37 links (24.42'), Spruce 12 S38W 18 links (11.88'). 2014: Found
1" pipe and witnesses by unknown persons.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E06) Accepted found old wood post with three additional post points in muck. Also mounds
corresponding to the original Bearing Trees. Several trees with iron marks in vicinity. Position is
accepted as a careful and faithful PERPETUATION of the position of the original corner.

(E07) Accepted found 1" pipe (set by unknown persons) and two existing NBT's with witness Nails and
overgrowth facing said Pipe. SW NBT has a location tag (Sid Dye 1980 & TAN 1989). Set new nails
above existing nails (existing are flush with the bark at this time). Position is accepted as a
careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E06) DNR monument
10" Tamarack N43E 16.14' (1/4S,NBT)
6" B. Spruce S40E 8.13' (1/4S,NBT)
7" Tamarack WEST 15.87' (1/4S,NBT)
10" Tamarack N26W 35.00' (1/4S,NBT)
All trees are blazed, scribed, painted,
and signed. Measurements are to nail in
side of tree, bearings are magnetic. A
Metal sign post was set North 1.5 feet.
Signed by
Surveyor's Michigan License No. 50447
(E07) DNR monument
6" Spruce N78E 33.32' (S16,NBT)
EX 23" W. Pine S70W 12.28' (- , -)
15" W. Pine S70W 12.28' (S17,NBT)
EX 22" W. Pine N39W 14.48' (- , -)
All trees are blazed, scribed, painted,
and signed. Measurements are to nail in
side of tree, bearings are magnetic. A
Metal sign post was set North 1.5 feet.
Date August 25, 2014

Surveyor's Michigan License No. 50447

20418
20419



Table with 13 rows and 13 columns (A-M). Contains numbers 1-36 in a grid pattern, likely a reference for section numbers.