

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

for corners in

Menominee (County) Located In: Corner Code #
Public Land Survey T 41N R 26W G02
T 41N R 26W G03
Property Controlling Section S T R
S T R
S T R
Miscellaneous Property in Sec. S T R
S T R

1. Lot No. , Recorded Plat
2. Private Claims

8/14/2014
Jeremy J. Pipp, in a field survey on 8/14/2014 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

(G02) Quarter corner common to Sections 3 and 4. 1852: E.C. Martin, DS. Set quarter section post
witnessed by W. Pine 20 S80W 18 links (11.88'), Fir 10 N60E 21 links (13.86'). No evidence of
subsequent establishment.

(G03) Section corner common to Sections 3, 4, 9, and 10. 1852: E.C. Martin, DS. Set section post
witnessed by Tamarack 16 S60W 28 links (18.48'), Cedar 8 N48E 21 links (13.86'). No evidence of
subsequent establishment.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G02) No evidence of original survey. Searched several stump mounds in area; no post points or soil
stains recovered. Corner position reestablished by single proportionate measurement between the
Northwest corner and the Southwest corner of Section 3. Position is accepted as a careful and
faithful REESTABLISHMENT of the position of the original corner.

(G03) No evidence of original survey. Corner position reestablished by double proportionate
measurement using existing corners one mile North, one-half mile East, one mile South, and one &
one-half miles West. Found recent wood post N73W 3.5 feet from monumented position; no other post
points or corresponding original evidence found. Position is accepted as a careful and faithful
REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 2 columns: (G02) DNR monument and (G03) DNR monument. Rows include tree types (Poplar, Spruce, Cherry) and measurements (N44E 13.44', S53E 71.09', etc.).

All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic. A Metal sign post was set North 1.5 feet.

Signed by [Signature] Date August 25, 2014
Surveyor's Michigan License No. 50447
For the Michigan Department of Natural Resources, Forest Restoration



Register of Deeds Stamp & File Number. Grid with columns A-M and rows 1-13. Contains numbers 6-36 and two black dots in row 2, column G and row 3, column G.